

Technical Memorandum Soil Excavation Optimization



Parcel C Remedial Action Remedial Units C1, C2, C4, and C5 Hunters Point Naval Shipyard San Francisco, California

Lora Battaglia


Project Manager
Support Contractor to NAVFAC BRAC PMO
BRAC Program Management Office West

BCT Meeting March 28, 2013



Parcel C Excavations as presented in FS, ROD, and RD







Tech Memo



The following location types where COCs are present in soil at concentrations exceeding RGs were considered:

- Tier 1 locations: excavation areas where soil concentrations are greater than the RRGs as established in the ROD (Tier 1 action levels).
- Tier 2 locations: excavation areas where soil concentrations are greater than 5 times the RRGs (Tier 2 action levels).
- Tier 3 locations: excavation areas where soil concentrations are greater than 10 times the RRGs (Tier 3 action levels).

Note: Tier action levels apply to metals and PCBs only. The action levels for TPH, VOCs and pesticides are equal to the RRGs in all tiers. Similar tiered approaches have been used in Parcels E and E-2 at HPNS.



Soil Excavation Tech Memo



Meeting March 19th: Action Items

1) Ensure that all 4 of the RUC2 excavations are incorporated into the RUC2 Final Work Plan, using the same rationale as applied to RUC 1, 4 and 5, and if not, issue change pages.

No change pages needed. Excavations will be conducted per the RAWP. Depth of excavation will be determined by confirmation samples collected 1' below depth of previous RG exceedance.

- 2) Agency comments on RUC1, 4, 5 Draft RAWP and Tech Memo due 3/29
- 3) Navy preparing table identifying which excavations may require a change to ROD, if any, and which will be "optimization" of the RD.
- 4) Navy to provide additional detail in Tech Memo regarding how we came to optimizing excavations and the history of this transition
- 5) Navy and contractor to work closely with Risk Assessor on revising Tech Memo language and putting together a risk communication strategy



Soil Excavation Tech Memo



- 6) Navy to provide additional detail regarding what contaminants are left in place once a Tier is applied and why those will be left in place; specifically related to risk related to:
 - future land use
 - groundwater contamination
 - proximity to the bay/migration potential
 - manganese left in place

Navy to revise tech memo for the following:

- 7) indicate that confirmation sampling will follow RAWP/SAP protocol
- 8) have consistent colors and legends throughout figures
- 9) focus explanation on risk rather than statistical significance
- 10) support no further action where removals have been completed



Soil Excavation Tech Memo



Navy to revise tech memo for the following:

- 11) be consistent in descriptions of changes from RD (no change/reduce depth)
- 12) add average depth that prior radiologic excavations have been completed
- 13) remove language in Tech Memo referring to additional analysis beyond the 95%UCL.

Navy to provide:

- 14) redline/strikeout version of Tech Memo and RAWP
- 15) Proposal for administratively documenting changes to ROD. Plus consider City's request to apply changes to areas beneath buildings.
- 16) Navy to consider notifying public at next meeting of any approved changes.



RUC1



Site	Original FS Volume (bcy)	Excavation Optimization Plan	Depth	Original Excavation Volume (bcy)	Optimized Excavation Volume (bcy)	Volume Difference (bcy)	Change to ROD
RU-C1		,					
22-1	14,568	No change; excavate originally proposed volume.	no change	14,599	14,599	0	No
22-2	141	Tier 2. Excavation is complete. No further remedial action necessary.	Excavation complete	141	0	(141)	Yes
COS-2-1	117	No change; excavate originally proposed volume.	no change	117	117	0	No
COS-2-2	90	Data error. No further remedial action necessary.		90	0	(90)	N/A



RUC4



				Original Recalc	Optimized Excavation	Volume	
	Original FS Volume			Volume	Volume	Difference	
Site RU-C4	(bcy)	Excavation Optimization Plan	Depth	(bcy)	(bcy)	(bcy)	Change to ROD
23-1	10,233	Tier 3 (or Tier 2). Reduce footprint based on 10x RRG for metals, PCB.	Varies: 10x RRG for metals and PCBs based on deepest known conc	10,268	1,852	(8,416)	Yes
23-2	259	Excavation is complete. No further remedial action necessary, pending confirmation sample results.	Confirm removal by verifying depth and location of Tt excavation	260	0	(260)	No
23-3	89	Excavation is complete. No further remedial action necessary, pending confirmation sample results.	Confirm removal by verifying depth and location of Tt excavation	89	0	(89)	No
24-1	453	No change; excavate originally proposed volume.	no change	451	451	0	No
24-2	182	Reduce excavation depth from 10.2 to 2.75 ft bgs based on confirmation sample results.	2.75'	182	50	(132)	No
24-3	142	Tier 2. Excavation is complete. No further remedial action necessary because sample is so close to RRGs.	Excavation complete	143	0	(143)	Yes
24-4	215	Reduce footprint based on confirmation sample results.	9'	167	121	(46)	No
24-5	387	Tier 3 (or Tier 2). Reduce footprint based on confirmation sample results.	7'	385	26	(359)	Yes
24-6	384	Reduce excavation depth from 10.2 to 7 ft bgs based on confirmation sample results.	7'	385	262	(123)	No
26-1	79	Excavation is complete. No further remedial action necessary.	Verify sample is removed - TPH program	79	0	(79)	No
26-2	89	Reduce excavation depth from 10.9 to 4.75 ft bgs based on confirmation sample results.	4.75'	91	40	(51)	No
CMI-1	435	Reduce excavation depht from 9.4 to 4.25 ft bgs based on confirmation sample results	4.25'	435	192	(243)	No



RUC5



Site	Original FS Volume (bcy)	Excavation Optimization Plan	Depth	Original Excavation Volume (bcy)	Optimized Excavation Volume (bcy)	Volume Difference (bcy)	Change to ROD
RU-C4							
23-1	10,233	Tier 3 (or Tier 2). Reduce footprint based on 10x RRG for metals, PCB.	Varies: 10x RRG for metals and PCBs based on deepest known conc	10,268	1,852	(8,416)	Yes
23-2	259	Excavation is complete. No further remedial action necessary, pending confirmation sample results.	Confirm removal by verifying depth and location of TI excavation	260	0	(260)	No
23-3	89	Excavation is complete. No further remedial action necessary, pending confirmation sample results.	Confirm removal by verifying depth and location of TI excavation	89	0	(89)	No
24-1	453	No change; excavate originally proposed volume.	no change	451	451	0	No
24-2	182	Reduce excavation depth from 10.2 to 2.75 ft bgs based on confirmation sample results.	2.75'	182	50	(132)	No
24-3	142	Tier 2. Excavation is complete. No further remedial action necessary because sample is so close to RRGs.	Excavation complete	143	0	(143)	Yes
24-4	215	Reduce footprint based on confirmation sample results.	9,	167	121	(46)	No
24-5	387	Tier 3 (or Tier 2). Reduce footprint based on confirmation sample results.	7'	385	26	(359)	Yes
24-6	384	Reduce excavation depth from 10.2 to 7 ft bgs based on confirmation sample results.	7'	385	262	(123)	No
26-1	79	Excavation is complete. No further remedial action necessary.	Verify sample is removed - TPH program	79	0	(79)	No
26-2	89	Reduce excavation depth from 10.9 to 4.75 ft bgs based on confirmation sample results.	4.75'	91	40	(51)	No
CMI-1	435	Reduce excavation detph from 9.4 to 4.25 ft bgs based on confirmation sample results	4.25'	435	192	(243)	No



Building 241 Area



				,		T	
Site	Original FS Volume (bcy)	Excavation Optimization Plan	Depth	Original Recalc Excavation Volume (bcy)	Optimized Excavation Volume (bcy)	Volume Differenc (bcy)	ce Change to ROD
Building 241							
18-1	179	Reduce excavation depth from 10.7 to 8 ft bgs based on confirmation sample results.	8.	178	133	(45)	No
18-2		Reduce footprint based on confirmation sample results and previous removal actions. Reduce excavation depth from 9.6 to 7.75 bgs based on confirmation sample results.	7.75'	284	80	(204)	No
18-3	2,856	No change; excavate originally proposed volume.	no change	2,868	2,868	0	No
18-4	189	Excavation is complete. No further remedial action necessary.	Confirm removal by verifying depth of Tt excavation	189	0	(189)	No
Totals:			I	42,368	25,746	(16,622)	
			Summary volumes not considering typical overexavation rate of	f 10-15%.			
Notes:			Including over-excavation rate (10%)):	28,320	(14,048)	
bcy - bank cubic yards							
bgs - below ground surface							
ft - feet					Total Volume Reduction associated with ROD Deviation:		
RU - Remedial Unit							
			10				



Administrative Documentation



- Type of change
 - Nonsignificant or minor change
 - Evaluated based on
 - Scope
 - Performance
 - Cost
- Memo to file



Schedule Update



- Draft Tech Memo issued for review 3/14/2013
- Tech Memo meeting 3/19/2013
- BCT comments on Draft Work Plan 3/29/2013
- Final Work Plan to be issued 5/13/2013
- Field work to begin (May 2013)
 - Based on radiological work completed, excavations will begin in area RU-C5

DRAFT

TECHNICAL MEMORANDUM Soil Excavation Optimization Parcel C Remedial Action Remedial Units C1, C2, C4, and C5 Hunters Point Naval Shipyard San Francisco, California

Contract Number: N62473-10-D-0807 Contract Task Order: 0008

Document Control Number: SHAW-0807-0008-0195

March 2013

Submitted t





Base Realignment and Closure Program Management Office West Naval Facilities Engineering Command 1455 Frazee Road, Suite 900

Submitted by:



Shaw Environmental & Infrastructure, Inc. (a CB&I company) 4005 Port Chicago Highway, Suite 200 Concord, California 94520-1120